



कार्यालय नगरपंचायत बेसा पिपळा



ता.जि.नागपुर

E-mail-npbesapipla@gmail.com

जावक क./न.प.बे.पि/स्व.वि. 2609/2025

दिनांक: 26/06/2025

Water and Sanitation Certificate

It is certified that an inspection team headed by Water supply and Sanitation Engineer from Nagar Panchayat Besa-Pipla inspected School Of Scholars, Beltarodi, Besa Road on 10/07/2025 and on the basis of Water Test Report (Attached) bearing no SOS25-269048 dated 16/07/2025 of Water Resources Department certified that School Of Scholars, Beltarodi has safe drinking water facilities for the students and members of staff of the institution. The School also maintains the hygienic sanitation condition in the school building & the campus as per norms prescribed by the Central/State/U.T. Govt. This certificate is valid for a period of 1 year.

Signature with Seal: 

Name.... Bharat Nandanwar

Designation.... Chief officer

Name & Address of the Office /Department:

To

School Of Scholars, Beltarodi

Besa-Pipla Road,

Nagpur





Government of Maharashtra
Water Resources Department

Hydrology Project Division, Nagpur,
Water Quality Lab Level-II, Nagpur.

R. No. RQ91/5633

Jal Vidyan Bhavan, Wainganga Nagar, Ajni Nagpur - 440003.

AN ISO 9001 : 2015 CERTIFIED LABORATORY

No. 99

W.Q.LAB LEVEL-II/NAG/2024

Date: 16/07/2025

Sample Analysis Report

Name and Address of Client: School Of Scholars Beltarodi, Nagpur.	Date of Sampling	11/07/2025
	Sample Collected by	Client
	Date of Sample receipt in Lab	11/07/2025
	Sample I.D. Number	DW/2507/004
Reference	Your letter dated: 02/07/2025	
Sample Description	RO Water Sample	

Sr. No.	Characteristic (Parameter)	Unit	Analysis Result	DRINKING WATER - SPECIFICATION	
				Requirement (Acceptable Limit)	Permissible Limit in the Absence of Alternate Source
1	Colour	Hazen unit	<1	5 Max	15 Max
2	Odour	--	Agreeable	Agreeable	Agreeable
3	pH	--	7.9	6.5 To 8.5	No relaxation
4	Turbidity	NTU	0.1	1 Max	5 Max
5	Total Dissolved Solids	mg/L	108	500 Max	2000 Max
6	Total Alkalinity (as CaCO ₃)	mg/L	72	200 Max	600 Max
7	Chloride (as Cl ⁻)	mg/L	13.0	250 Max	1000 Max
8	Total Hardness (as CaCO ₃)	mg/L	76	200 Max	600 Max
9	Calcium (as Ca)	mg/L	20.0	75 Max	200 Max
10	Magnesium (as Mg)	mg/L	6.3	30 Max	100 Max
11	Fluoride (as F)	mg/L	0.06	1.0 Max	1.5 Max
12	Sulphate (as SO ₄)	mg/L	10.2	200 Max	400 Max
13	Nitrate (as NO ₃)	mg/L	0.98	45 Max	No relaxation
14	Iron (as Fe)	mg/L	0.05	0.3 Max	No relaxation
15	Total Coliforms	MPN/100ml	Absent	Shall not be detectable in any 100 ml sample	
16	Fecal Coliforms	MPN/100ml	Absent	Shall not be detectable in any 100 ml sample	

End of Report



for Government Analyst
Water Quality Lab Level-II
Hydrology Project, Jalvigyan Bhavan,
Wainganga Nagar, Ajni,
NAGPUR